

411-6 Screening & Buffering Standards

| | SCREENING & BUFFERING TYPE | REQUIRED PLANT UNITS PER 100 LINEAL FEET | ADDITIONAL SETBACK OPTIONS (IN FEET) | PLANT UNIT MULTIPLIER | STRUCTURE REQUIRED (SEE SECTION 411-7) |
|---------|---------------------------------------|---|---|------------------------------|---|
| 411-6.1 | #1 | 2 Canopy trees | 5.0 | 1.0 | S-1 |
| | | 2 Understory trees | 7.5 | 0.8 | None |
| | | | 10.0 | 0.6 | None |
| | | | 12.5 | 0.4 | None |
| 411-6.2 | #2 | 2 Canopy trees | 5.0 | 1.0 | S-1 |
| | | 4 Understory trees | 7.5 | 0.8 | S-1 |
| | | | 10.0 | 0.6 | S-1 |
| | | | 12.5 | 0.4 | S-1 |
| 411-6.3 | #3 | 4 Canopy Trees | 10.0 | 1.0 | S-2 |
| | | 4 Understory trees | 15.0 | 0.8 | S-2 |
| | | 10 Shrubs | 20.0 | 0.6 | S-1 |
| 411-6.4 | #4 | 5 Canopy trees | 15.0 | 0.9 | S-3 |
| | | 10 Understory trees | 20.0 | 1.0 | S-2 |
| | | 15 Shrubs | 25.0 | 0.8 | None |
| | | | 30.0 | 0.6 | None |
| 411-6.5 | #5 | 6 Canopy trees | 25.0 | 0.6 | S-4 |
| | | 9 Understory trees | 30.0 | 0.75 | S-3 |
| | | 36 Shrubs | 40.0 | 1.0 | B-2 or S-2 |
| | | 18 Evergreen/conifer trees | 50.0 | 0.8 | B-1 or S-2 |
| | | | 75.0 | 0.6 | None |
| 411-6.6 | #6 | 10 Canopy trees | 40.0 | .6 | BW3 |
| | | 15 Understory trees | 75.0 | .8 | BW2 |
| | | 60 Shrubs | 100.0 | 1.0 | BW1 or S-4 |
| | | 30 Evergreen/conifer trees | 115.0 | 1.0 | None |
| | | 30 Evergreen/conifer trees | 125.0 | .8 | None |